



REQUEST FOR COMMISSION ACTION
CITY OF INDEPENDENCE
March 10, 2022

Department Administration/Public Works

Director Approval David Cowan/John Garris

AGENDA ITEM Consider authorizing TranSystems to prepare and submit a KDOT Cost Share Program grant application for: Sycamore, 10th to 21st.

SUMMARY RECOMMENDATION Authorize submissions.

BACKGROUND Kansas Department of Transportation (KDOT) Cost Share applications for state fiscal year 2022/2023 are due on March 17, 2022.

4" mill, 2" overlay, new sidewalk ramps, addition of a 10'x5' box culvert at Sycamore.

Estimated Cost	Estimated City Match – (15%)	Non-Participating Costs	Total City Cost
\$972,983	\$119,247	\$178,000	\$297,247

Staff believes we should resubmit this application for state fiscal year 2024, (July 1, 2023 – June 30, 2024).

SUGGESTED MOTIONS I move to authorize TranSystems to prepare an application for KDOT's Cost Share Program for Sycamore from 10th Street to 21st Street and to submit the application to KDOT.

SUPPORTING DOCUMENTS Cost Estimate

Opinion of Probable Construction Cost
City of Independence, Kansas
Cost Plus
Sycamore Street from 10th to 21st, New Curb & Gutter, Mill & Overlay
and Ramp Replacement

ITEM NO.	PARTICIPATING BID ITEM	UNIT	UNIT BID PRICE	QUANTITY	COST
1	Contractor Construction Staking	LSUM	\$5,000.00	1.0	\$ 5,000.00
2	Mobilization	LSUM	\$30,000.00	1.0	\$ 30,000.00
3	Clearing & Grubbing	LSUM	\$5,000.00	1.0	\$ 5,000.00
4	Milling (4 inches)	S.Y.	\$4.00	18277.0	\$ 73,108.00
5	Asphalt (2 inches)	Ton	\$110.00	2500.0	\$ 275,000.00
6	Concrete Patching, 8"	S.Y.	\$120.00	100.0	\$ 12,000.00
7	4" Concrete Sidewalk	S.Y.	\$60.00	350.0	\$ 21,000.00
8	Ramps (4")(AE)	S.Y.	\$150.00	100.0	\$ 15,000.00
9	Box Culvert under Sycamore	LSUM	\$35,000.00	1.0	\$ 35,000.00
10	Rock Excavation	C.Y.	\$70.00	650.0	\$ 45,500.00
11	4" Base Rock	S.Y.	\$10.00	450.0	\$ 4,500.00
12	Curb and Gutter (in place)	LF	\$30.00	7900.0	\$ 237,000.00
13	Traffic Control	LSUM	\$15,000.00	1.0	\$ 15,000.00
14	Permanent Striping	L.F.	\$2.50	8750.0	\$ 21,875.00

City Cost

Construction	\$	794,983	\$	119,247
Design	\$	78,000	\$	78,000
Inspection	\$	100,000	\$	100,000
Estimated Total	\$	972,983	\$	297,247

- 4" Milling and 2" overlay
New Curb and Gutter Along Sycamore St and to the Curb Return on Side Streets
New sidewalk ramps
Add 10x5 box culvert at Sycamore (storm sewer South of Sycamore not eligible under program)